



# GENERAC® STANDBY GENERATOR ACCESSORIES

## DLM Load Control Module



### DESCRIPTION

The DLM Load Control Module is a 50 amp contact housed in a NEMA 3R enclosure for indoor and outdoor installation applications. Through the use of the DLM Modules in conjunction with any of the 100-400 amp Nexus Smart Switches, household or business loads can be intelligently managed enabling the use of a smaller, more efficient generator system. Up to four DLM Modules can be used with a single switch.

### SPECIFICATIONS

Power Supply Source .....	Contactor module is supplied with 120VAC from the load control module in the transfer switch.
Nominal Supply .....	120VAC
Coil VA Inrush .....	30
Coil VA Sealed .....	6.5
Poles .....	2
Voltages .....	120/240
Resistive Amps .....	50
F/L Inductive Amp .....	40
Locked Rotor Amps .....	240@240V
UL 50 .....	Yes



## DIMENSIONS

