16644



# Call Us First! DO NOT RETURN TO STORE.

For immediate help with assembly or product information

call our toll free number: 1-800-577-9663 or email:

### customerservice@backyardproductsllc.com


Our staff is ready to provide assistance April through October M-F 8:00 AM to 4:30 PM EST Saturday 8:30 AM to 4:30 PM EST November through March M - F 8:00 AM to 5:00 PM EST (This page intentionally left blank.)



# MANSFIELD GABLE 10' x 12' (305 x 366 cm)

ACTUAL FLOOR SIZE IS 120 x 144" (304,8 x 365,8 cm)

**KEEP THIS MANUAL FOR FUTURE REFERENCE** 



# 🛆 IMPORTANT! 🛆

### **READ INSTRUCTIONS THOROUGHLY PRIOR TO BEGINNING ASSEMBLY.**

# **BEFORE YOU BEGIN**

### • BUILDING RESTRICTIONS AND APPROVALS

Be sure to check with local building department and homeowners association for specific restrictions and/ or requirements before building

#### ENGINEERED DRAWINGS

Contact our Customer Service Team if engineered drawings are needed to pull local permits.

#### • SURFACE PREPARATION

To ensure proper assembly you must build your shed on a level surface. Recommended methods and materials to level your shed are listed on page 7.

#### CHECK ALL PARTS

Inventory all parts listed on pages 4 - 6. Contact our Customer Service Team if any parts are missing or damaged.

### ADDITIONAL MATERIALS


You will need additional materials to complete your shed. See page 3 for required and optional materials and quantities.



# - CUSTOMER SERVICE -




Call: 1-800-577-9663 email: customerservice@backyardproductsllc.com



# **ORIENT LUMBER AND TRIM FOR BEST APPEARANCE**


Framing lumber is graded for structural strength and not appearance. Exterior trim is graded for one good side.

Always install the material leaving the best edge and best surface visible. Please remember that these blemishes in no way negatively affect the strength or integrity of our product. (See Fig. A, B, C.)





ADDITIONAL MATERIALS						
FOUNDATION OR FLOOR MATERIALS						
This shed does not include any floor or leveling materials.						
See the FLOOR LEVELING section on page 8 for recommended floor, as this will vary depending on your specific site.	d methods and suggested materials to properly level your					
WOOD FLOOR FRAME						
MATERIAL REQUIRED: Use only wood treated for ground	contact and fasteners approved for use with treated wood.					
	2 x 4 x 120" (5,1 x 10,2 x 304,8 cm)					
x2 TREATED						
2 x 4 x 144" (5,1 x 10,2 x 365,8 cm)	Hot Dipped Galvanized Box-Type Nails.					
	3" (7,6 cm)					
<b>FLOOR PANELS</b> You will need floor panels and nails to complete your floor. Floor panel sizes and quantities are shown below.						
NOTE: Use a minimum of 5/8" (1,6 cm) Oriented Strand Board (OSB)						
<b>X3</b> 5/8" x 48" x96" (1,6 x 121,9 x 243,8 cm)	<b>x1</b> 2" (5,1 cm) <b>1</b> lb. of 2" (5,1 cm) Hot Dipped Galvanized Box-Type Nails.					
REINFORCED WOOD FLO	OOR FRAME (OPTIONAL)					
<b>IMPORTANT!</b> The included floor has been designed for general the second distribution of the second di						
$\mathbf{x3}$ 2 x 4 x 10' (5 x 10 x 304,8 cm) Treated Lumber	low as shaded). Below is a list of additional materials (not included):					
Cut to (3) 2 x 4 x 117" (5 x 10 x 297,2 cm)						
<b>x12</b> ea. 3" (7,6 cm) Hot Dipped Galvanized Nails	→ Optional 12" (30,5 cm) spacing → Standard 16" (40,7 cm) spacing					
COMPLETING	YOUR SHED					
You will need these	additional materials:					
3-TAB SHINGLES 7 Bundles	<b>1" GALVANIZED ROOFING NAILS 3 Lbs</b> For shingles.					
PAINT FOR SIDING	PAINT FOR TRIM         1 Quart           Use 100% acrylic latex exterior paint.					
CAULK	WOOD GLUE Exterior Rated					
OPTIONAL MATERIALS						
DRIP EDGE 60 Feet	#15 ROOFING FELT					
	To cover 148 Sq. Ft. of roof area.  1" GALVANIZED ROOFING NAILS1/4 Lb					
	For roofing felt.					
REFER TO THE BACK OF THIS MANUAL AND THE MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION OF SHINGLES, DRIP EDGE AND FELT.						

PARTS IDENTIFICATION AND SIZES								
Part identification letters are stamped on some parts.			. Treated lumber is stamped:		WOOD SIZE CONVERSION CHART Nominal Board Size Actual Size			
			TDEATE		2" x 4"1-1/2" x 3-1/2" (3,8 x 8,9 cm) 1" x 4"3/4" x 3-1/2" (1,9 x 8,9 cm)			
RS RS			TREATED		2" x 3"1-1/2" x 2-1/2" (3,8 x 6,3 cm)			
Check these locations for part stamp.					1" x 3"3/4" x 2-1/2" (3,8 x 6,3 cm)			
	PARTS LIST							
			gest sorting parts by th		are listed in.			
	□ x1	<b>GAA</b> 1 x 3 x 5" (2 5	x 7,6 x 12,7 cm) Gauge Block for	3/4" (1.9 cm) measureme	ent //~ 3/4"			
			1/2" (5,1 x 10,2 x 21,6 cm)		(1,9 cm)			
			x 12-1/2" (5,1 x 10,2 x 31,8 cm)					
	☐ x2	AO	2 x 4 x 22-1/2" (5,1 x 10,2 x	x 57,1 cm)				
S	□ × <b>-</b>	RL	 2 x 4 x 24" (5,1 x 10,2 x 6 <sup>2</sup>	1 cm)				
WALLS	<b>x</b> 4	STL	 2 x 4 x 44-1/2" (5,1	,				
MA	□ x4	SP		x 10,2 x 121,9 cm)				
	x2	AM		2 x 4 x 67" (5,1 x 10,3 x <sup>2</sup>	170,2 cm)			
	x6	YFA		] 2 x 4 x 68-1/2" (5,1 x 1	10,2 x 174 cm)			
	x26	ТК		2 x 4 x 80	)" (5,1 x 10,2 x 203,2 cm)			
	<b>x4</b>	ТР			2 x 4 x 96" (5,1 x 10,2 x 243,8 cm)			
	x10	6 x 24"	(15,2 x 61 cm) <b>OSB OR WOOD G</b>					
S		<b>CLA</b> 2 x 4 x 4-7/8"	(5,1 x 10,2 x 12,4 cm)					
Ä		<b>PVA</b> 2 x 4 x 5-7/8	8" (5,1 x 10,2 x 14,9 cm)					
F	□ x1			] 1 x 3 x 72" (1,6 x 7,6 x <sup>2</sup>	182.9 cm)			
RAFTERS				-				
	<b>X8</b>	ECA		/ 2 x 4 x 75-1/4" (5	i,1 x 10,2 x 191,1 cm)			
	⊥ x10	ECN	~	2 x 4 x 75-1/4" (5	i,1 x 10,2 x 191,1 cm)			
	<b>x4</b>			3/8 x 1-3	3/4 x 81-7/8" (1 x 4,4 x 208 cm)			
	<b>x</b> 4			3/8 x 1	-3/4 x 82-1/2" (1 x 4,4 x 209,6 cm)			
	<b>x1</b>	ZJ		] 19/32 x 3 x 72" (1,5 x 3	7,6 x 183 cm)			
M	<b>x</b> 4			3/8 x 7-7/8 x 73	3-5/16" (1 x 20 x 186,2 cm)			
TRIM	<b>x</b> 2			3/8 x 4-3/4	4 x 75-7/8" (1 x 12,1 x 197,2 cm)			
	<b>x</b> 2			3/8 x 4-3/4	1 x 75-7/8" (1 x 12,1 x 197,2 cm)			
	<b>x4</b>			3/8 x 5-7/8 >	x 72-3/4" (1 x 14,9 x 184,8 cm)			
	x4			3/8 x 4-3	3/4 x 80-5/8" (1 x 12,1 x 204,8 cm)			
	<b>x1</b>	/GTL	/ 19/32	x 3 x 50-1/4" (1,5 x 7,6 x	: 127,6 cm)			
DOOR	x1	/GTR	/ 19/32	x 3 x 50-1/4" (1,5 x 7,6 x	: 127,6 cm)			
00	<b>x</b> 4	AH	] 19/32 x 3 x 26-5/8" (1,5 x 7,6 x	67,6 cm)				
7	<b>x</b> 2	00		1-1/2 x 2-1/2 x 69" (3,	8 x 6,3 x 175,3 cm)			
			2	1				



WORK BENCH PARTS						
x6R	2 x 3 x19" (5,1 x 7,6 x 48,3 cm)					
x1 JS	1 x 4 x 23-7/8" (2 5 x 10 2 x 60 6 cm)	/8 x 14-1/4 x 22-1/4" (1 x 36,2 x 56,5 cm)				
X1 KP	1 x 4 x 5	96" (2,5 x 10,2 x 243,8 cm)				
<b>x1</b>	-7/8" x 92-1/2" (1,1 x 60,6 x 235 cm)	/16 x 23-7/8" x 20-1/2" (1,1 x 60,6 x 52,1 cm)				
	SHUTTERS					
<b>x4 KV</b> 19/32 x	<b>x1 BWR</b> 19/32 x 3 x 21" (1,5 x 7,6 x 5)	3,3 cm) <b>x2 AH</b> 19/32 x 3 x 26-5/8" (1,5 x 7,6 x 67,6 cm)				
<b>x6 AZ</b> 19/32 x	<b>x1 BWL</b> 3 x 30-1/8" (1,5 x 7,6 x 76,5 cm) 19/32 x 3 x 21" (1,5 x 7,6 x 5					
	FASTENERS & HARDWA	ARE				
	NAIL BOXES (no	t included)				
X4 BOXES	3" (7,6 cm	))				
X7 BOXES	2" (5,1 cm)					
	FASTENER/HARDWARE	BAG				
x100	1-1/2" (3,8 cm)					
x310	[ 2" (5,1 cm)					
🗌 x140 🕂	)	)				
🗌 x16  🕂	→ 2" (5,0 cm)					
<b>x55</b>	00000000000000000000000000000000000000	<b>x2</b> 3/8" x5-1/2" (1 cm x 14 cm) Hex Bolt				
🗌 x132 🕂	2000000000 3/4" (1,9 cm)	<b>X4 Flat Washer</b>				
<b>x20</b> (+)	000000000000- 1" (2,5 cm)	<b>x2</b> $\langle \bigcirc^{3/8" (1 \text{ cm})}$ Lock Nut				
<b>x8</b> (+)	(Januarian 1" (2,5 cm)					
	VENT/ DOOR HARDWARE/ V					
□x2 □ x1 □ x1	Window $22-1/2" \times 29-3/4"$ $(57,1 \times 75,6 \text{ cm})$ $\mathbf{x1}$ Handle (locking) $1-1/4" \times 2$ $1-1/4" \times 2$ $1-1/4" \times 2$ $1-1/4" \times 2$ $\mathbf{x1}$ $\mathbf{x1}$					
	mmm 3/4" (1,9 cm) x11 ged separately / special coating	x1				





- Level under 4x4 runners only.
- Locate leveling material 12" from ends of runners and no more than 48" apart.
- Asphalt shingles should be used between 4x4 runners and blocks or treated lumber. Never use shingles in direct contact with ground.
- For best results and aiding in water drainage use gravel under each concrete block.

# LEVELING MATERIALS

Gravel

Solid Masonry Blocks in 1", 2", 4" or 8" thickness

2x4 Treated Lumber

Asphalt Shingles


# Leveling higher than 16" not recommended.

# CONCRETE

• If you are building your shed on a concrete foundation see the following page.

# **CONCRETE FOUNDATION**

Your kit contains all materials to construct a wooden floor. If you choose to install your kit on a concrete slab refer to the diagram below.




Allow new concrete slabs to cure for at least seven (7) days.


- A treated 2 x 4" (5,1 x 10,2 cm) sill plate is required when installing your shed on concrete. Hint: Use treated lumber in your kit or purchase full length treated lumber.
- Use a high quality exterior grade caulk beneath all sill plates.
- Fasten 2 x 4" (5,1 x 10,2 cm) sill plates to slab using approved concrete anchors (fasteners not included).
- Check local code for concrete foundation requirements.




# TO ASSEMBLE YOUR FLOOR - PLEASE REFER TO INSTRUCTIONS PROVIDED WITH YOUR FLOOR KIT.

# **IMPORTANT!**







BEGIN

Place two rafters **ECN** into the jig as shown.


2

Keep **ECN** firm against outside **PVA**'s as shown (**Fig.A**) and push rafters tight to the middle **PVA**. Rafters should touch at tips (**Fig. A**).

Apply glue to rafters where gusset will attach (Fig. B).


Place gusset onto **ECN** holding a 1/4" gap from edge (**Fig. C**) and keeping rafters firm as instructed. Secure gusset using one 1-5/8" screw into each rafter. **HINT:** These screws will help hold the measurements when you nail on gussets.


Use ten 2" nails to finish securing the gusset to the rafters to pattern shown in Fig. C.




Flip rafters over and attach a second gusset using glue and (12) 2" nails. No need to use jig for this gusset.

Repeat steps 1 through 3 to assemble four more rafters.











HINT:
 For easier nailing stand on frame.


Orient parts on edge on floor as shown. Use two 3" nails as shown.Use two 3" nails at each mark and four 3" nails at seams.


















Nail using 2" nails 6" apart on edges and 12" apart inside panel.






9 You have finished building your BACK WALL.





Place 48" x 84" panel with primed side up onto frame flush at top and with a 3/4" gap on right side.
 Maintain 3/4" measurement along edge.


3 Secure panel to frame using 2" (5,1 cm) nails 6" (15,2 cm) apart along edges.




		GABLE WALL	,	
PA	RTS REQUIRED:		x90 📄	
<b>x1</b>	23-7/8 x 84" (60,6 x 213,4 cm) <b>x1</b>		48 x 84" (122 x 213,4 cm)	2" (5,1 cm)


Place **23-7/8" x 84"** primed side up and flush with installed **48" x 84"** panel edge. Ensure panel is flush at top. Secure using 2" (5,1 cm) nails 6" (15,2 cm) apart on edges.


5 Place **48" x 84"** primed side up and flush with installed **23-7/8" x 84"** panel edge. Ensure panel is flush at top. Secure using 2" (5,1 cm) nails 6" (15,2 cm) apart on edges and 12" (30,5 cm) apart on inside of panel.






You have finished standing your BACK WALL.








7 Nail lower edge of panels to floor frame using 2" nails 6" apart. Angle nail to hit floor frame (Fig. D).


8 Secure front wall bottom plates to floor using 3" nails (Fig. D).





FINISH 10 You have finished standing your FRONT WALL.

# GABLE WALL INSTALLATION




### 

**Remove Temporary Supports** and stand gable wall on floor.



Set gable wall on floor and secure using one 2" screw on each side (Fig A).

### $\triangle$ ensure top wall frames are flush. $\triangle$



2 Move to the bottom of gable wall and secure bottom of wall using one 2" screw into eave wall bottom plate (Fig B).


L ENSURE WALL PANELS ARE FLUSH BEFORE SECURING.

# **GABLE WALL INSTALLATION**

### PARTS REQUIRED:




Nail lower edge of panels to floor using 2" nails 6" apart. Angle nail to hit floor frame (Fig. C).



You have finished standing your GABLE WALL.

5

6




1

2


6

You will build TWO assemblies. Orient RL and ECA on flat as shown.


Place LEFT front gable panel as shown and secure using 1-1/2" nails.



Place MIDDLE front gable panel flush to installed left panel. Ensure panels are flush. 3 Secure panel to installed RL using 1-1/2" nails. Place second RL as shown under MIDDLE panel and secure using 1-1/2" nails.





Place RIGHT front gable panel flush to installed middle panel. Ensure panels are flush. Secure to RL using 1-1/2" nails.



Repeat **Steps 1-4** to build second gable panel.


FINISH You have finished assembling your gable panels.






Orient gable and ladder assemblies as shown (Fig. E). You will build TWO complete assemblies.

8 Ensure gable panels are flush at peak of ladder and flush along top edge of ladder assembly. Secure using 1-5/8" screws as shown (Fig. E).




9 Attach PVA to ladder assembly using 3" screws (Fig. F).



10 Repeat Steps 7-9 to build the other gable assembly.

FINISH 1 You have finished building two gable units.



Measure 1-1/2" down from top plate and mark at each side as shown. Set gable unit on top plate.

Continue nailing lower edge of panels into top plate using 2" nails 6" apart as shown

#### RL RL Fig. A **TOP PLATE** - 6" (15,2 cm) 1-1/2" NAIL FIRST 1-1/2" NAIL FIRST (3,8 cm) 2" (5,1 cm) 2" (5,1 cm) (3,8 cm) Measure and Measure and 3" Mark Mark (7,6 cm) Screws

Then, on the inside, secure gable unit with 3" screws toe-screwed into RL at an angle as shown in (Fig. B).

Repeat Steps 1-3 to attach left gable unit.

/ It is important to secure the gable unit in the following order:

L BE SURE GABLE IS CENTERED ON WALL BEFORE NAILING.

Hold secure with one 2" nail on each side as shown.


1


2

3


4

Secure gable with two 3" screws toe-screwed into **RL** at an angle as shown in (**Fig. B**).





You have finished attaching your TRUSSES.




# **ROOF PANELS**

### **PARTS REQUIRED:**


3 Attach another 27-1/4" x 32-5/8" roof panel, rough side up, flush with the installed 27-1/4" x 96" panel (Fig. C) and flush with the rafter ends (Fig. B).

0 -

Secure panel with two 2" (5,1 cm) nails in the corners.




4 Nail the roof panel using 2" nails 6" apart on edges and 12" apart inside panel.




## **ROOF PANELS**

#### PARTS REQUIRED:



# ROOF PANELS


7 Nail the roof panels using 2" nails 6" apart on edges and 12" apart inside panel.






8 Repeat process to attach roof panels on the opposite side.








You have finished installing your soffit panels.

#### Ensure soffit boards are flush at rafter ends (Fig. B) and flush at seams.

Position **72-3/4**" soffit boards **primed side down** flush to gable soffits and rafter ends (**Fig A**). Toenail at center seam (**Fig. C**). Secure using eight 2" finish nails, two in each rafter.



2 Repeat **Step 1** to attach eave side soffit boards on the opposite side.


# FINISH

You have finished installing your eave side soffit panels.



1 Position fascia with **primed side out** and flush to peak and roof panels as shown (**Fig. A, Fig B**). Secure using 2" finish nails spaced evenly as shown.









Repeat Steps 1-2 to attach fascia boards on the other gable end.

# FINISH

You have finished installing your gable fascia.





Position two **4-3/4" x 80-5/8"** fascia boards with **primed side out**, flush with roof panels and gable fascia as shown (**Fig. A**). Secure using 2" finish nails into rafter ends.





You have finished installing your eave side fascia.

1










6 Position horizontal door rails **AH** onto outside of doors. Measure, mark and hold.


Secure **AH** using 3/4" screws from inside (**Fig C**).






Center metal threshold between doors and secure using eleven 3/4" special coating screws into floor as shown (Fig. D).

#### (11) Special Coating Screws




FINISH
 9 You have finished attaching your door trim and threshold.



3 Repeat Steps 1-2 to install OO on right door.

FINISH 4 You have finished installing your door stiffeners.



# PARTS REQUIRED:


1/2" (13 mm) Drill Bit 1/4" (6 mm) Drill Bit


Measure and mark location of hole on outside of right door as shown (Fig. A). Pre-drill hole with 1/4" drill.

2


2 Re-drill hole with 1/2" drill (Fig. B).

Keep drilled hole square to trim to avoid breaking edge of 1-1/2" x 2-1/2" door stiffener.








Secure backplate with 1" screws and handle with 1-1/4" screws as shown.



See following pages for mounting locations of brackets and plates.







# **CORNER TRIM**

**x48** 

2" (5,1 cm)

#### PARTS REQUIRED:

x4

x4

#### 3/8 x 1-3/4 x 82-1/2" (1 x 4,4 x 209,6 cm)

3/8 x 1-3/4 x 81-7/8" (1 x 4,4 x 208 cm)

#### 

2

Attach one **81-7/8**" trim board flush under soffit panel and against eave wall (Fig. A, B) using one 2" finish nail at top as shown.


Position 82-1/2" trim board flush along edge of 81-7/8" trim board and flush under gable panel (Fig. A, B). Secure using one 2" finish nail at top as shown.

Finish attaching trim flush to corners (Fig. B) using six 2" (5,1 cm) finish nails as shown.



# FINISH

You have attached your corner trim.









Fig. A




5 Locate **TP** and **RL** flush to bottom of top plate and aligned at seam. Secure with 3" (7,6 cm) nails at wall studs and seam.




6 Clamp or hold **Pre-Assembled Loft Joist** in place flush under top plate as shown. Drill through joist and wall studs with 7/16" drill bit as shown.




7 Secure joist with hex bolts, flat washers and lock nuts at both sides (Fig. B). Tighten lock nuts securely.







8 Install loft panel centered over loft joists. Secure with 2" (5,1 cm) nails 8" (20,3 cm) apart. There will be a gap of approximately 8-1/2" on either side.




Attention: Load not to exceed 400 lbs (181 kg) evenly distributed across loft.







Secure **AE** to bracket panels using three 2" (5,1 cm) nails. Assemble 6 shelf supports as shown; 5 right-side, 1 left-side.






2 Secure shelf supports at shown height with three 2" (5,1 cm) nails.







3 Install shelf panels centered over shelf supports. Secure with 2" (5,1 cm) nails at each support.




Secure **KP** and **JS** with 2" (5,1 cm) nails at each support as shown.

Δ







Secure LR to bracket panels using three 2" (5,1 cm) nails. Assemble 6 shelf supports as shown; 5 right-side, 1 left-side.




2 Secure work bench supports at shown height with three 2" (5,1 cm) nails.







Install work bench panels centered over bench supports. Secure with 2" (5,1 cm) nails at each support.



Secure **KP** and **JS** with 2" (5,1 cm) nails at each support as shown. 4






2


1 Position and level collar tie on third rafter from loft.

HINT: For best appearance install collar tie on rafter facing away from door opening.


Attach with 2" nails as shown.



FINISH 3 You have finished installing your collar tie.








# WINDOW & SHUTTERS x4 1-1/4" (3,2 cm) Vindow 22-1/2" x 29-3/4" (57,1 x 75,6 cm) Image: Colspan="2">Image: Colspan="2" Image: Colspan="2" Image





Seal window with high-quality exteriorgrade caulk before installing (Fig. A).



Attach window using four 1-1/4" (3,2 cm) screws as shown. Ensure window is level.







#### PAINT & CAULK - NOT INCLUDED -


- Use acrylic latex caulk that is paintable. Caulk at all horizontal and vertical seams, between the trim and walls, and all around the door trim.
- Use a high quality exterior acrylic latex paint. When painting your building, there are a few key areas that can be easily overlooked that must be painted:
  - Bottom edge of all siding and trim
  - · Inside of doors and all 4 edges

#### Note:


Prime all un-primed exterior wood before painting. (Follow directions provided by manufacturer.)



• Install felt flush to all roof edges overlapping 3". Use minimal amount of roofing nails to hold in place.



- Install drip edge over roof felt on gable side and under roof felt on eave side (Fig. A).
- Do not use nails on side of drip edge that hangs over side of building.
- Only nail top of drip edge as shown.




# SHINGLES


Follow directions provided by manufacturer and these instructions.



/I Familiarize yourself with a 3-Tab Shingle.



Install first starter row upside down and color up with a 1" overhang at back and bottom of roof panel. Use (4) nails per shingle. **Starter row must be straight and level all the way across with lower edge of roof deck. NOTE:** If you have installed drip edge install shingles flush to drip edge.




#### SHINGLES continued...


Beginning at front of shed, install first row of shingles with notch at 1" past roof edge or flush with drip edge.

2

3




Install second row of shingles flush at top of first row's rain slots. Ensure 1" overhang or flush to drip edge at front, stagger each row.




### SHINGLES continued...

5

Continue installing rows of shingles to the peak. At the peak make sure there is a maximum of 5" or less to the rain slot, as shown below. If shingles overlap at ridge cut to peak with a utility knife.






• If more than 5" to rain slot you must install another row of shingles.

6 Repeat steps 1 - 5 to shingle the opposite side of your roof. Trim shingles at ridge.

Once both sides are shingled you need to trim ends. Strike a chalk line 1" from edge.




Using your shingle hooked blade carefully cut shingles along chalk line.





# SHINGLES - RIDGE CAP



FRONT OF SHED Flush

# SHINGLES - RIDGE CAP continued...


Continue installing ridge cap to back of roof.

4


5

6


7




Make sure there is 4" between the shingle-color and edge of shingles.



When you have 4" minimum of shingle color cut one piece to cap your roof.





FINISH You have finished your ridge cap. 8

Install flush to shingles.

#### WARRANTY REGISTRATION

Please complete your warranty registration to properly validate your warranty.

Register your product online at: www.OnlineWarranty.net

#### LIMITED CONDITIONAL WARRANTY\*

Backyard Storage Solutions, LLC warrants the following:

- 1. Every product is warranted from defects in workmanship and manufacturing for 1 year.
- 2. All accessories, hardware and metal components are warranted for 2 years.
- 3. All Oriented Strand Board (OSB) is warranted for 2 years
- 4. Siding and Trim is warranted for:
  - 10 years: Value Series / Solar Shed
    - 12 years: Classic Series / Architectural Series
  - 15 years: Big Buildings
- 5. Solar Shed windows are warranted for 1 year.
- 6. Cedar lumber is warranted for 15 years.
- 7. Preserved Pine is warranted for 10 years.

Backyard Storage Solutions, LLC will repair, replace or pay for the affected part. In no event shall Backyard Storage Solutions, LLC pay the cost of labor or installation or any other costs related thereto. All warranties are from date of purchase. If a cash refund is paid on an affected part, it will be prorated from the date of purchase.

#### CONDITIONS

The warranty is effective only when:

- 1. The unit has been erected in accordance with the assembly instructions.
- 2. The unit has been properly shingled and painted or stained and reasonably and regularly maintained thereafter.
- 3. The failure occurs when the unit is owned by the original purchaser.
- 4. Backyard Storage Solutions, LLC has received the warranty registration card within thirty (30) days of purchase and notification of the failure in writing within the warranty period specified above.
- 5. Backyard Storage Solutions, LLC has had reasonable opportunity during the sixty (60) days following receipt of notification to inspect and verify the failure prior to commencement of any repair work.

#### REQUIREMENTS

#### **Storage Buildings**

To validate your warranty, it is necessary to properly maintain your Backyard Storage Solutions, LLC unit; shingle the roof and paint or solid-colored stain the siding using quality, 100% acrylic latex exterior product with a minimum of two (2) coats within thirty (30) days of assembly; caulk above all doors and all horizontal and vertical trim boards; paint and seal all exposed edges, sides and faces of siding/trim and OSB siding to include all exterior walls and all sides and all edges of doors.

#### Gazebos & Pergolas

To validate your warranty, it is necessary to properly maintain your Backyard Storage Solutions, LLC unit. This includes treating all of the exposed cedar and pine surfaces on your gazebo or pergola structure with an exterior grade wood preservative, an exterior oil-based semi-transparent stain, an acrylic latex exterior paint or an acrylic latex solid color exterior stain within 30 days of assembly and as needed thereafter to maintain your warranty.

Keep vegetation trimmed away from building and make sure siding panels and trim do not come in contact with masonry or cement. The minimum ground clearance for siding must be one half inch (½ inch) from concrete slab or two and one half inches (2 ½") from the ground when building is erected or constructed on a treated wood floor kit. Water from sprinklers must be kept off unit. In no event will Backyard Storage Solutions, LLC be responsible for any indirect, incidental, consequential or special damages nor for failure(s) that are caused by events, acts or omissions beyond our control including, but not limited to, misuse or improper assembly, improper maintenance (which eventually leads to rot or decay) and acts of God. Backyard Storage Solutions, LLC will not be held responsible for any labor costs incurred to construct your unit.

This warranty gives you certain specific rights that vary from state to state.

#### **CLAIM PROCEDURE**

To make a claim under this warranty, you can either call 1-888-827-9056 or email: customerservice@backyardproducts.com. Please have ready the information below when you call or include the information in your email:

- 1. The model and size of the product.
- 2. A list of the part(s) for which the claim is made.
- 3. Proof of purchase of the Backyard Storage Solutions, LLC item, as shown on the original invoice.
- 4. Run code: found on exterior product label or assembly instructions enclosed in the product package.

All other inquiries can be mailed to:

Backyard Storage Solutions, LLC Attn: Customer Service 1000 Ternes Monroe, MI 48162 **\*WAR** 

\*WARRANTY TERMS MAY VARY OUTSIDE THE U.S.A. IMPORTANT: This is your warranty certificate.