

CEMENT BOARD MATERIALS ESTIMATOR & COVERAGE

TOTAL AREA (Square Feet)	CEMENT BOARDS NEEDED		CEMENT BOARD TAPE (Feet)	SCREWS (WALL)		SCREWS (FLOOR)	
	3'x5'	4'x8'		3'x5' (Count)	4'x8' (Count)	3'x5' (Count)	4'x8' (Count)
15	1	1	50	36	25	54	43
30	2	1	50	72	50	108	86
45	3	2	50	108	74	162	128
60	4	2	50	144	99	216	171
75	5	3	50	180	124	270	214
90	6	3	50	216	149	324	257
105	7	4	50	252	173	378	299
120	8	4	50	288	198	432	342
135	9	5	50	324	223	486	385
150	10	5	100	360	248	540	428
165	11	6	100	396	272	594	470
180	12	6	100	432	297	648	513
195	13	7	100	468	322	702	556
210	14	7	100	504	347	756	599
225	15	8	100	540	371	810	641

We recommend the following tools to complete your project:

- Safety goggles
 - Safety gloves
 - Tape measure
- T-square or straight edge
 - Utility knife and extra blades
 - Hammer
- 1/4" trowel
 - Thin-set mortar
 - Screw gun